

Vinton Trail Master Plan



Trail Issues

1. MAY REQUIRE PARKING RESTRICTIONS
2. REQUIRES AGREEMENT WITH RAILROAD FOR AT-GRADE OR AERIAL CROSSING

Trail Cost Opinion

GRADING FOR HARD-SURFACED TRAILS, 14' WIDE	\$6,000
PAVEMENT REMOVAL	\$1,125
UTILITY ADJUSTMENTS	\$1,000
STORM SEWER/CULVERTS	\$2,500
4" GRANULAR SUBBASE	\$3,000
5" PCC TRAIL, 10' WIDE	\$16,800
NEW 4" SIDEWALK	\$71,000
ADA CURB RAMP TREATMENT	\$9,600
SEEDING/FERTILIZING/MULCHING	\$600
BIKE RACK/BENCHES	\$1,000
TRAIL BRIDGE	\$280,000
PAINTED PAVEMENT SYMBOLS	\$2,550
TRAIL SIGNAGE	\$6,000
ESTIMATED CONSTRUCTION COST	\$401,180
25% CONTEGENCY AND ENGINEERING	\$100,295
TRAIL SEGMENT TOTAL COST	\$501,475

THESE COSTS ARE BASED ON OCTOBER 2008 DOLLARS AND SHOULD BE ADJUSTED TO THE ANTICIPATING BIDDING DATE.

Eastside Trail Segment

